

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-163-20165-00-00

RECEIVED
STATE CORPORATION COMMISSION
JAN 7 1969
CONSERVATION DIVISION
Wichita, Kansas
1-7-69

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Rains & Williamson, Three G and Petroleum, Inc.

Complete Address: 1525 Wichita Plaza Wichita, Kansas

Lease Name Havlas Well No. 1

Location SW SW NE 2200' FNL & 2200' FEL Sec. 15 Twp. 9 Rge. 18 (E) (W) XX

County Rooks Total Depth 3518'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated: _____

Plugging Contractor: Rains & Williamson

Address: Wichita, Kansas License No. _____

Operation Completed: Hour 2:30A Day 3 Month 1 Year 1969

The Above well was plugged as follows:

RTD 3518' 8 5/8 csg set at 225' cwc Cmt. Mat. 50-50 poz cmt. W/6% total gel.

Gunned pits, circulated heavy mud, set cementing plug at 720' and displaced 70 sk cmt.

thru drill pipe. Heavy mud to 210' set cementing plug and displaced 20 sk cement thru

drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to base

of cellar. Plugged rat hole with 2 sk cmt.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo F. Massey
Well Plugging Supervisor

DATE 1/7/69

INV. NO. 9160-u