

DISTRICT CONSERVATION AGENT'S REPORT

15-163-03242-00-00

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. \_\_\_\_\_

LOCATION NW NW SW

SEC. 19 TWP. 9 RGE. 18

Dry Hole  Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 1 Lease Jelinek

Operator B & R Drg Co Inc Address Russell, Kans

Field \_\_\_\_\_ County Rooks

Total Depth 3636 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 283' circulated with 160 sax cement - 5 1/2" at

3622' with 75 sax cement behind.

Filled with chat to 3610', set 4 sax cement with dump bailer,

pulled 2500' 5 1/2", filled hole with mud to 280', set rock and

15 sax cement, mud to 35', set rock and 10 sax cement to

bottom cellar.

**RECEIVED**  
STATE CORPORATION COMMISSION

MAY - 3 1952

CONSERVATION DIVISION  
Wichita, Kansas

Edmond Perry  
District Conservation Agent

Date 5-1-52

**PLUGGING**  
FILE NO. 19T-9-R-182  
BOOK 13 PAGE 27

5-3-52