

DISTRICT CONSERVATION AGENT'S REPORT

15-163-03243-00-00

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 107-6

LOCATION SW SE SE

SEC. 19TWP. 9 RGE. 18

Dry Hole X Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 2 Lease Gilbert

Operator Continental Oil Co Address Ponca City

Field \_\_\_\_\_ County Rooks

Total Depth 3672 Feet.

(Describe briefly the manner in which the well was plugged)

10" at 213' circulated with cement - 5 1/2" at 3669' with 75  
sax cement behind - perforations at 3613'.

Filled with sand to 3600', set 4 sax cement with dump bailer,  
pulled 3000' 5 1/2", filled with mud to 213', set rock bridge  
and 20 sax cement, mud to 30', set rock and 10 sax cement  
to bottom cellar.

**PLUGGING**  
FILE SEC 19 T 9 R 18  
PAGE 107 UNIT 6

**RECEIVED**  
STATE CORPORATION COMMISSION  
JUN 22 1953  
CONSERVATION DIVISION  
Wichita, Kansas

Edwin T. ...  
District Conservation Agent  
Date 6-19-53

6-22-53