

DISTRICT CONSERVATION AGENT'S REPORT

R

TO:

15-163-03273-00-00

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 65-40

LOCATION SW SW NW

SEC. 19 TWP. 9 RGE. 18

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease Hilger

Operator Sinclair Oil & Gas Address Box 551 Chase, Kans

Field _____ County Rooks

Total Depth 3591 Feet.

Plugging Contractor West Supply Co

Plugging Contractor's License No. 14

Address _____

(Describe briefly the manner in which the well was plugged)

10 3/4" at 281' circulated with cement - 7" at 3584' with 150

sax cement behind - Lane Wells plugs to 3465' perforated 3423'.

Filled with sand to 3400', set 5 sax cement with dump bailer,

pulled 1100' 7", filled with mud to 280', set rock and 20 sax

cement, mud to 30', set rock and 10 sax cement to bottom cellar.

Edna Petty
District Conservation Agent

Date 10-2-54

RECEIVED
STATE CORPORATION COMMISSION

OCT - 7 1954

CONSERVATION DIVISION
Wichita, Kansas

10-7-54

PLUGGING

FILE SEC 19 T. 9 R. 18
BOOK PAGE 105 LINE 40