

KANSAS

Form CP-3  
Rev. 6-26-62

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-163-19172-00-01

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 17 1969  
CONSERVATION DIVISION  
Wichita, Kansas  
3-17-69

Operator's Full Name Robert R. Price

Complete Address: P. O. Box 45442-Southeast Station Tulsa, Oklahoma 74115

Lease Name Wilkinson Well No. 1

Location NE (SW) NE Sec. 19 Twp. 9 Rge. 18 (E) (W) XX

County Rooks Total Depth 3712'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated: (OWWO)

Plugging Contractor: Southwest Casing Pulling

Address: Box 364 Great Bend, Kansas License No. 399

Operation Completed: Hour 1P Day 14 Month 3 Year 1969

The Above well was plugged as follows:

Total Depth 3712' 8 5/8 csg set at 209' cwc 150 sk.

5 1/2 csg set at 3712' cw 150 sk cmt.

Filled 5 1/2 csg W/sd (3700-3712) Dumped 5 sk cmt W/dump bailer. (3660-3700)

Cutoff and recovered 1300' of 5 1/2 csg.

Pumped thru 8 5/8 plug container With 25 sk gel W/5 sk hulls, plug and 130 sk 50-50

poz cmt. W/6% total gel. Max. pres. 250 lbs. SI pres 250 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 3/17/69  
INV. NO. 9472-11

Signed: Pro J. Murphy  
Well Plugging Supervisor