

**KANSAS**  
**STATE CORPORATION COMMISSION**

**CONSERVATION DIVISION AGENT'S REPORT**

15-163-19173-00-00

**RECEIVED**  
STATE CORPORATION COMMISSION

OCT 14 1965  
10-14-65  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Bergman Oil Co

Complete Address: 425 Union Center Wichita, Kans

Lease Name Hilgers Well No. B-1

Location NE NE SE Sec. 19 Twp. 9 Rge. (E) (W) 18

County Rooks Total Depth 3664'  
5364'

Abandoned Oil Well x Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Knight Casing Pulling Co

Address: Chase, Kans License No. 436

Operation Completed: Hour 2PM Day 12 Month 10 Year 65

The Above well was plugged as follows:

8 5/8" 225' circulated with cement - 4 1/2" 3364' with 150 sax cement

Set plug at 2900', sand to 2850', set 4 sax cement with dump bailer.

pulled 2397' 4 1/2" to 550', circulated hole with heavy gel mud throught

4 1/2" ( 20 sax Gel), displaced 20 sax cement through 4 1/2" at 500', heavy

mud to 200', displaced 20 sax cement through 4 1/2" at 200', heavy mu d

to 35', set 10 sax cement to bottom cellar.

Mudding and cementing by Knight Company pump truck.

I hereby certify that the above well was plugged as herein stated.

Signed: Eldon Peery  
Well Plugging Supervisor

**INVOICED**  
DATE 10/14/65  
INV. NO. 1948-4