

DISTRICT CONSERVATION AGENT'S REPORT

R

15-163-00148-00-00

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. _____

LOCATION NW NW NW

SEC. 30 TWP. 9 RGE. 20 *W*

Dry Hole _____ Abandoned Oil Well Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease Baldwin

Operator Nadel & Gussman Address Box 509 Tulsa, Okla

Field _____ County Rooks

Total Depth 3875 Feet.

Plugging Contractor Barnes & Sons

Plugging Contractor's License No. 9

Address _____

(Describe briefly the manner in which the well was plugged)

8 5/8" at 190' circulated with cement - 5 1/2" at 3872' with 75 sax
cement behind.

Filled with sand to 3860', set 4 sax cement with dump bailer,
pulled 920' 5 1/2" - filled with mud to 185', set rock and 15 sax
cement, mud to 35', set rock and 10 sax cement tonbottom cellar.

PLUGGING
FILE NO. 15-163-00148-00-00
PAGE 22-LINE 6

RECEIVED
STATE CORPORATION COMMISSION
DEC 7 - 1955
12-07-1955
CONSERVATION DIVISION
Wichita, Kansas

Leon Perry
District Conservation Agent
Date 12-2-55