

DISTRICT CONSERVATION AGENT'S REPORT

15-163-02542-00-00

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION NE NW NW

SEC. 30 TWP. 9 RGE. 20W

Dry Hole Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 2 Lease Baldwin

Operator Nadel & Gussman Address Wichita, Kans

Field _____ County Rooks

Total Depth 3882 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 176' circulated with cement - 5 1/2" at 3874' with
100 sax cement behind- Lane Wells plugs to 3775' & top perforations
at 3616'.

Filled with chat to 3600', set 5 sax cement with dump bailer,
pulled 3200' 5 1/2', filled hole with mud. to 176', set rock and
15 sax cement, mud to 35', set rock and 10 sax cement to bottom
cellar.

RECEIVED

02-27-1952

FEB 27 1952

PLUGGING
PAGE SEC 30 T 9 R 20W
BOOK PAGE 147 LINE 25

CONSERVATION DIVISION District Conservation Agent
Wichita, Kansas

Date 2-26-52