

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

15-163-20531-00-00

RECEIVED
STATE CORPORATION COMMISSION
JUN 21 1974
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Jet Drilling Co. Inc.
Complete Address 514 One Twenty Bldg., Wichita, Kansas
Lease Name Brillhart Well No. 1
Location NE NW SW Sec. 30 Twp. 9 Rge. (E) (W) 20
County Rooks Total Depth 3915'
Abandoned Oil Well Gas Well Input Well SWD Well D & A XX
Other well as hereafter indicated
Plugging Contractor L. Chief Drlg.
Address Wichita, Kansas License No.
Operation Completed: Hour 12:45 P. Day 19 Month 6 Year 1974

The above well was plugged as follows:

RTD 3915' 8 5/8 csg set at 241' cwc Cmt. Mat. 50-50 poz 6% total gel.
Gunned pits, circulated heavy mud, set cementing plug at 720' and displaced 70 sk
cmt thru drill pipe. Heavy mud to 215' set cementing plug and displaced 20 sk cmt
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to
base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo F. Massey
Well Plugging Supervisor

INVOICED

DATE 6/24/74
INV. NO. 9362-W