

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

APR 19 1961
04-19-1961
CONSERVATION DIVISION
Wichita, Kansas

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

15-163-01777-00-00

File No. _____ County: _____ Rooks
Location: CS $\frac{1}{2}$ SE NW Sec. 34 Twp. 9 Rge. 20 (E) (W)
Name of Field: _____ Total Depth: 3862

I have this date completed supervision of plugging of:

Lease Name: Darrell Well No. 5

Operator's Full Name: Fender Pipe & Supply Co

Complete Address: Box 302 Russell, Kansas

Plugging Contractor: Barnes & Sons

Address: Russell, Kansas License No. 9

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No

If yes how long? _____ Reason: _____

Operation Completed: Hour 2PM Day 16 Month 4 Year 61

The above well was plugged as follows:

8 5/8" 296' circulated with cement. 5 1/2" 3857' with 100 sax cement/.
Filled with sand to 3840', set 4 sax cement with dump bailer, pulled
2927' 5 1/2" to 500', circulated hole with heavy mud (18 sax Gel), displaced
20 sax cement through 5 1/2" at 500', heavy mud to 160', displaced 20 sax
cement through 5 1/2" at 160', heavy mud to 35', set bridge and 10 sax cement
to bottom cellar.

Mudding and cementing by Globe Cementing Co.

Signed: [Signature]
Conservation Division Agent

Reviewed: [Signature]
Field Supervisor

Remarks:

INVOICED

DATE 4/28/61

INV. NO. 2988-4