

KANSAS

Y
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

NOV 9 1967

11-9-1967

CONSERVATION DIVISION
Wichita, Kansas

15-163-20074-00-00

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Dane G. Hansen Estate

Complete Address: Logan, Kansas

Lease Name Coddington Well No. 10

Location App. C NE/4 Sec. 34 Twp. 9 Rge. 20 (E) (W) X

County Rooks Total Depth 3866

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: C & G Drilling Company

Address: Wichita, Kansas License No. _____

Operation Completed: Hour 9:45 P Day 6 Month 11 Year 1967

The Above well was plugged as follows:

RTD 3866' 8 5/8 csg set at 176' cwc 150 sc.

Gunned pits; circulated heavy mud, set cementing plug at 970' and displaced 100 sc
cement thru drill pipe. Heavy mud to 180' set cementing plug and displaced 20 sc cem.
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement
to base of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Geo F. Massing
Well Plugging Supervisor

DATE 11/9/67

INV. NO. 6655-W