

DISTRICT CONSERVATION AGENT'S REPORT

15-065-03289-00-00

R

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 70-30

LOCATION SW SW NW

SEC. 8 TWP. 9 RGE. 21

Dry Hole Abandoned Oil Well X Abandoned Gas Well

I have this date completed supervision of plugging of:

Well No. 1 Lease Clack

Operator Shell Oil Co Address Box 744 Great Bend,

Field County Graham

Total Depth 3823 Feet.

Plugging Contractor Forbes Casing Pulling

Plugging Contractor's License No. 49

Address

(Describe briefly the manner in which the well was plugged)

8 5/8" at 1794' circulated with cement - 5 1/2" at 3820' with 100
saxv cement behind .

Filled with chat to 3810', set 4 sax cement wth dump bailer, pulled
3230' 5 1/2" - filled with heavy mud to 300', set rock and 15 sax cement,
mud to 35', set rock and 10 sax cement to bottom cellar.

PLUGGING
FILE SEC 8 T 9 R 21W
BOOK PAGE 20 LINE 30

001221954

CONSERVATION DIVISION
Wichita, Kansas

10-20-54

Edmund Kelly
District Conservation Agent

Date 10-21-54