

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

JAN 3 1972

CONSERVATION DIVISION  
Wichita, Kansas

1-3-72

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

15-065-~~6~~0000  
20515

Operator's Full Name Kedco Corporation, National Oil Company & B and B Drilling, Inc.,

Complete Address 816 Union Center, Wichita, Kansas.

Lease Name Teall Well No. 1

Location SE-SW-NE Sec. 8 Twp. 9 Rge. (E) (W) 21

County Graham Total Depth 3865'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated       

Plugging Contractor B and B Drilling, Incorporated,

Address 720 Union Center, Wichita, Kansas License No.       

Operation Completed: Hour 5:30 PM Day 29 Month 12 Year 1971

The above well was plugged as follows:

204'--8 5/8" Surface casing, cement circulated.  
Top of Dakota section @ 725'.

Circulated hole with heavy mud. Pulled DP to 950' and displaced 110 Cu. Ft. cement  
thru DP from 950' to 625'. Pulled DP to 215' and displaced 30 Cu. Ft. Cement thru  
DP from 215' to 140'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.  
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]  
Well Plugging Supervisor

DATE 1-11-72

INV. NO. 4963-W