

DISTRICT CONSERVATION AGENT'S REPORT

15-065-02316-00-00

*R*

TO:

State Corporation Commission  
Conservation Division  
211 North Broadway  
Wichita, Kansas

FILE NO. \_\_\_\_\_

LOCATION SW NE SW

SEC. 9 TWP. 9 RGE. 21W

Dry Hole  Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well \_\_\_\_\_

I have this date completed supervision of plugging of:

Well No. 3 Lease Clack 411 1st. Natl Bank Bldg,

Operator Barnett Oil Co Address Wichita, Kans

Field \_\_\_\_\_ County Graham

Total Depth 3740 Feet.

Plugging Contractor Forbes Casing Pulling

Plugging Contractor's License No. 49

Address \_\_\_\_\_

(Describe Briefly the manner in which the well was plugged)

8 5/8" at 150' circulated with cement - 5 1/2" at 3698' with 125  
sax cement behind.

Filled with sand to 3690', set 4 sax cement with dump bailer,  
pulled 2913' 5 1/2" - filled with heavy mud to 150', set rock and  
15 sax cement at 150', mud to 35', set rock and 10 sax cement  
to bottom cellar.

*Edwin Lee*

District Conservation Agent

11-8-56

Date

**RECEIVED**

STATE CORPORATION COMMISSION

NOV 13 1956

CONSERVATION DIVISION  
Wichita, Kansas

11-13-56

**PLUGGING**  
FILE SEC 9 T 9 R 21W  
BOOK PAGE 115 LINE 41