

15-163-22119-00-00

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE NAME Kaba
WELL NUMBER #1
SPOT LOCATION SW SW NW
SEC. 16 TWP 9S RGE. 18 (R) or (W)
COUNTY Rooks
Date Well Completed 9-8-83
Plugging Commenced 10-16-91
Plugging Completed 10-16-91

LEASE OPERATOR AFG Energy, Inc.
ADDRESS P.O. Box 605
PHONE # (913) 483-6213 OPERATORS LICENSE NO. 3456

Character of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes
Which KCC/KDHE Joint Office did you notify? _____
Is ACO-1 filed? Yes If not, is well log attached? _____

Producing formation Lan-KC & Arbuckle Depth to top 3205' bottom 3553 T.O. 3565

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Full State Corporation Commission
Arbuckle	Oil & Water	3547	53	8 5/8"	264	None
Lansing-KC	Oil & Water	3277	3454	5 1/2"	3586	None
Topeka	Oil & Water	3205	08			

RECEIVED

OCT 18 1991

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Ran tubing to 3085'-spotted 125 sx. 65/35 Poz, 8% gel. Pulled tubing to 1645. Circulated to surface with 100 sx. of same. Hooked to 8 5/8" and pumped 100 sx. of same down casing & circulated up 5 1/2" casing. Closed 8 5/8" & hooked to 5 1/2" casing. Squeezed w/75 sx. of same. Max press - 300# STP - 200#.

(If additional description is necessary, use BACK of this form.)


Name of Plugging Contractor Allied Cementing, Inc. License No. _____
Address Russell, KS 67665

STATE OF Kansas COUNTY OF Russell, ss.

Terry W. Piesker (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Terry W. Piesker

(Address) P.O. Box 605, Russell, KS 67665



SUBSCRIBED AND SWORN TO before me this 17th day of October, 1991

Pamela K. Steckel
Notary Public

My Commission expires: 11-19-92