

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

15-163-01544-00-00

API NUMBER NA
 LEASE NAME Hilgers "A" #2
 WELL NUMBER 2

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

 Ft. from S Section Line
~~NW Cor of~~ Ft. from E Section Line

LEASE OPERATOR T. O. Rush
 ADDRESS 2301 IDA Lane - Hays, Ks
 PHONE#(913) 625-4957 OPERATORS LICENSE NO. 3846
 Character of Well Oil
 (Oil, Gas, B&A, SWD, Input, Water Supply Well)

SEC. 19 TWP. 9S RGE. 18 (E or (W)
 COUNTY Rooks
 Date Well Completed 6-18-1956
 Plugging Commenced 5-31-91
 Plugging Completed 6-3-91

The plugging proposal was approved on June 19, 1991 (date)
 by Mr. Don Butcher (KCC District Agent's Name).

Is ACO-1 filed? yes If not, Is well log attached? No

Producing Formation Toronto Depth to Top 3312 Bottom 3316 T.D. 3574

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

10-8-91
 RECEIVED

Formation	Content	From	To	Size	Put in	Pulled out
	Surface Pipe	0	140'	8 5/8	140'	- 0 -
Heebner shale	Dry	3290	94	5 1/2	3573	- 0 -
Toronto	Oil - water	3308	13	5 1/2	3573	- 0 -
LANSING	Oil - water	3331	36	5 1/2	3573	- 0 -
Arbuckle	Oil - water	3574	90	5 1/2	3573	- 0 -

STATE CORPORATION COMMISSION

OCT 08 1991

CONSERVATION DIVISION
 WICHITA, KANSAS

Describe in detail the manner in which the well was plugged, (indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Ran 5 1/2" Packer on 2" tubin To 2670' & set mixed cement & squeezed to 500 lbs Pulled & layed Down Packer Ran 2" tubin open ended to 1600' Spot 1 sk Hull 100 sks of cmt Pulled tubin To 860' Spot 3 sks of Hulls 60 sks of cmt Per P csg 850'-52 Spot cmt @ 500' circ to Surf. Tied on 8 5/8" csg cmt w/ 30 sks of cmt To surface Press. 400 lbs. shut in - 30 sks cmt Down 5/2 300 lb shut in
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Lyons Well Service License No. 30375
 Address 1103 S. ST. JOHN Lyons Well Serv Hays, Ks 67554
 NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: T. O. Rush Oil
 STATE OF Kansas COUNTY OF Ellis, ss.

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Tom Rush

(Address) 2301 Ida Lane Hays, Ks

ED AND SWORN TO before me this 17th day of October, 19 91

Kelly Leiker
 Notary Public



My Commission Expires: 2-25-95