

15-163-03065-00.00

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Rooks County. Sec. 19 Twp. 9 Rge. 18 (E) (W)

Location as "NE/CNW/SW" or footage from lines C W/2 NW SW

Lease Owner Osage Oil & Gas Co., Inc.

Lease Name Jelenik Well No. 1

Office Address 709 Petroleum Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed January 21 1957

Application for plugging filed January 21 1957

Application for plugging approved January 21 1957

Plugging commenced January 21 1957


Plugging completed January 21 1957

Reason for abandonment of well or producing formation oil in commercial quantities not found

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

NORTH



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3642 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	174'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with extra heavy rotary mud from total depth to 170'. Set #1 plug at 170' with 15 sacks cement, 1/2 sack Hulls. Filled hole with extra heavy rotary mud from #1 plug to 40'. Set #2 plug at 40' cemented with 10 sacks cement, 1/2 sack Hulls.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Prime Drilling Company

Address 814-16 Union Center, Wichita, Kansas

STATE OF KANSAS, COUNTY OF Sedgwick, ss.

R. R. McNicol (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R.R. McNicol

814-16 Union Center, Wichita, Kansas

(Address)

January, 19 57


Darlene May Notary Public.

RECEIVED
STATE CORPORATION COMMISSION

JAN 30 1957

CONSERVATION DIVISION
Wichita, Kansas

1-30-57



PLUGGING
FILE SEC 19 T 9 R 18 W
BOOK PAGE 136 LI E 8

15-163-03065-00-00

ROTARY DRILLING LOG

OPERATOR: Osage Oil and Gas Co., Inc.
Jelinek No. 1
C W/2 NW SW Sec. 19-9-18,
Rooks County, Kansas

CONTRACTOR: Prime Drilling Company
COMM: 1/11/57
COMP: 1/21/57

Remarks: Set 8-5/8" surface casing
at 174' cemented with 100 sacks
Pozmix, 2% C.C.

Formations:

Clay Shale & Post Rock	85'
Sand	115'
Shale	174'
Shale & Shells	250'
Gray Shale	540'
Shale & Shells	900'
Sand & Shale	1290'
Red Bed & Shale	1570'
Anhydrite	1610'
Shale & Shell	1890'
Shale & Lime	2320'
Lime & Shale	2795'
Shale & Lime	2825'
Lime & Shale	3005'
Shale & Lime	3055'
Lime & Shale	3090'
Shale & Lime	3125'
Lime & Shale	3185'
Lime	3585'
Lime & Shale	3625'
Arbuckle Lime	3642'
Rotary Total Depth (D&A)	3642'

We certify the above log is true
and correct to the best of our
knowledge and belief.

PRIME DRILLING COMPANY

R.R. McNicol

R. R. McNicol

RECEIVED
STATE CORPORATION COMMISSION

PLUGGING
FILE SEC. 19 T. 9 R. 18W
BOOK PAGE 136 LINE 8 CONSERVATION DIVISION
Wichita, Kansas

JAN 30 1957

1-30-57