

15-163-19173-00-00


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

Rooks County. Sec. 19 Twp. 9 Rge. 18 (E) W (W)

Location as "NE/CNW&SW&" or footage from lines. NE NE SE  
Lease Owner Jay bergman Oil Company  
Lease Name Helger "B" Well No. 1  
Office Address Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole)  
Date well completed 19  
Application for plugging filed 19  
Application for plugging approved 19  
Plugging commenced 10-4-65 19  
Plugging completed 10-12-65 19  
Reason for abandonment of well or producing formation Depleted.

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty  
Producing formation Depth to top Bottom Total Depth of Well 3364 Feet  
Show depth and thickness of all water, oil and gas formations. 3064

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	225'	None
				4-1/2"	3364'	2396'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole, sanded hole to 2960' and dumped 4 sacks of cement @ 2960' with dump bailer. Pulled 4 1/2" casing to 550' and circulated pipe with 25 sacks of gel mud. Pulled pipe to 500' and pumped in 20 sacks of cement. Pulled 4 1/2" casing to 200' and pumped in 20 sacks of cement. Pulled balance of 4 1/2" casing and capped hole with 10 sacks of cement.

RECEIVED  
STATE CORPORATION COMMISSION

DEC - 6 1965

CONSERVATION DIVISION  
Wichita, Kansas

PLUGGING COMPLETE.

12-6-65

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor KNIGHT CASING PULLING COMPANY  
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.  
Noel J. Knight (employee of owner) or (CONTRACTOR) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight  
Chase, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 20th day of October, 1965

Milton J. Volin  
Notary Public.

My commission expires May 20, 1968

15-163-19173-00-00

W E L L   L O G

HILGERS "B" #1 - NE NE SE  
Section 19-9S-18W  
Rooks County, Kansas

Date: Commenced: July 16, 1964  
Date Completed: August 1, 1964

Surface Casing: 160 feet with 225 Sacks Cement.  
Oil String: 3664 feet with 100 sacks cement.

0	-	40	Clay and Post Rock
40	-	158	Sand and Shale
158	-	850	Shale
850	-	1070	Shale and Shells
1070	-	1270	Dokata Sand
1270	-	1530	Shale and Shells
1530	-	1545	Anhydrite
1545	-	1568	Anhydrite
1568	-	1955	Shale and Shells
1955	-	2150	Shale and Lime
2150	-	2350	Lime and Shale
2350	-	2500	Lime and Shale
2500	-	2610	Lime and Shale
2610	-	2690	Shale and Lime
2690	-	2820	Shale and Lime
2820	-	2965	Shale and Lime
2965	-	3070	Shale and Lime
3070	-	3165	Lime
3165	-	3230	Lime
3230	-	3300	Lime
3300	-	3360	Lime
3360	-	3377	Lime
3377	-	3420	Lime
3420	-	3469	Lime
3469	-	3510	Lime
3510	-	3530	Lime
3530	-	3559	Lime
3559	-	3601	Lime
3601	-	3611	Arbuckle
3611	-	3626	Lime
3626	-	3660	Arbuckle
3660	-	3664	Arbuckle
3664			Rotary Total Depth


**RECEIVED**  
STATE CORPORATION COMMISSION

OCT 5 1965  
10-5-65  
CONSERVATION DIVISION  
Wichita, Kansas

A F F I D A V I T

STATE OF KANSAS     )  
                              )   SS.  
COUNTY OF SEDGWICK)

I do swear that the statements and matter herein contained are true to the best of my knowledge.



BERGMAN OIL COMPANY

Harold Bergman

Subscribed to and sworn to this 4th day of October, 1965.

Norma D. Dunsen  
Notary Public

My Commission Expires:  
August 2, 1966.