

15-163- 00302-00-00

## WELL PLUGGING RECORD

**Give All Information Completely**  
**Make Required Affidavit**  
**Mail or Deliver Report to:**  
**Conservation Division**  
**State Corporation Commission**  
**800 Biting Building**  
**Wichita, Kansas**

**NORTH**

A 4x4 grid with a small star in the top-right cell.

**Locate well correctly on above  
Section Plat**

## Rooks

County. Sec. 30 Twp. 9 Rge. 20 (E) (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NE corner

Lease Owner Nadel and Gussman

Lease Name Baldwin B Well No. 1

Office Address.....Drawer 309 Tulsa, Oklahoma.....

Character of Well (completed as Oil, Gas or Dry Hole) ..... Dry .....

Date well completed:.....4-23 1950.....

Application for plugging filed.....4-23 1950

Application for plugging approved.....4-23 1950.....

Plugging commenced ..... 4-23 1950

Plugging completed.....4-23 19 50.

Reason for abandonment of well or producing formation.....Dry.....

If a producing well is abandoned, date of last production: ..... 19.....

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well.....Mr. Pettie.....

Producing formation..... Depth to top..... Bottom..... Total Depth of Well 3940 Feet

Show depth and thickness of all water, oil and gas formations.

## OIL, GAS OR WATER RECORDS

### CASING RECORD

[illegible]

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from.....feet to .....feet for each plug set.

Hole-filled-with-heavy mud-from 3940 to 170' - Plug set at 170' - in surface pipe and cemented with 15 sacks cement. Top plug set at 30' and cemented with 10 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to.....Nadel and Gussman.....

Address..... P. O. Drawer 309, Tulsa, Oklahoma.....

STATE OF KANSAS, COUNTY OF SEDGWICK, ss. -

L. C. ~~XX~~ HAY.....(employee of owner) or (owner or operator) of the above-described well.

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) H. C. Bay

703 Union National Bank Bldg. Wichita,  
(Address)

(Address)

SUBSCRIBED AND SWORN to before me this 1st day of May, 1950

Notary Public.

My commission expires.....Nov. 3, 1952

\*\*\*\*\*  
· 22-7377-s                      4-49-10M

**PLUGGING**  
FILE SEC 30-T-9-R 206  
BOOK PAGE 2 LINE 43

15-163-00302-00-00

WELL LOG

Nadel and Gussman

Baldwin B No. 1

NEc 30-9-20W  
Rooks County, Kansas

Comm. 4-12-50  
Comp. 4-23-50

178' 8-5/8" Casing  
w/125 sacks cement

Formation

Shale and shells	725
Shale, sand and Pyrite	1150
Sand and shale	1515
Shale	1810
Anhydrite	1855
Shale and shells	2275
Broken Lime	2395
Shale and Lime	2670
Florence Flint	2700
Shale and Lime	3581
Lime	3865
Shale and Lime	3891
Shale	3908
Conglomerate	3940 T.D.

Elevation 2296'

Geological Tops

Topeka	3350'
Heebner	3559'
Toronto	3578'
Lansing-Kansas C.	3597'
Marmaton	3828'
Conglomerate	3908'

D & A.

STATE OF KANSAS )

SS:

COUNTY OF SEDGWICK )

L. C. Hay, of lawful age, being first duly sworn states that the above formations and tops are true and correct as taken from the daily drilling log of the Baldwin B No. 1 Well in the NE corner of Section 30, Twp. 9S, Rge 20W, Rooks County, Kansas.

L. C. Hay

Subscribed and sworn to before me this 1st day of May, 1950.

Notary Public

My Commission expires Nov. 3, 1952.

