


15-163-02542-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Rooks \_\_\_\_\_ County. Sec. 30 Twp. 9S Rge. (E) 20 (W)  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NE NW NW  
Lease Owner Nadel & Gussman  
Lease Name Baldwin Well No. 2  
Office Address Drawer 309, Tulsa 1, Oklahoma  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed February 26, 1952 19  
Application for plugging filed February 26, 1952 19  
Application for plugging approved February 26, 1952 19  
Plugging commenced February 26, 1952 19  
Plugging completed February 27, 1952 19  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3878 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	176'	None
				5 1/2"	3883'	3239'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plugged back with crushed rock to 3600'. Dumped 5 sacks with dump bailer, top of cement 3565'. Mudded hole to 176', set rock bridge, dumped 15 sacks cement. Top of cement 130'. Mudded hole to 90'. Finished  $\frac{1}{2}$  mudding hole to 35', set rock bridge, dumped 10 sacks cement for cap.

MAR 22 1952  
OEN 02-22-1952  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Nadel & Gussman  
Address Drawer 309, Tulsa 1, Oklahoma


STATE OF Oklahoma, COUNTY OF Tulsa, ss.  
Herbert Gussman (employee of owner) or (owner or operator) of the above-described well,  
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Herbert Gussman*  
Drawer 309, Tulsa 1, Oklahoma  
(Address)

SUBSCRIBED AND SWORN to before me this 15th day of March, 1952

My commission expires April 1, 1953. *Jack Brown* Notary Public.

23-3273-8 4-60-10M



PLUGGING  
FILE SEC 30 T 9 R 20  
BOOK PAGE 147 LINE 21

WELL LOG

NADEL AND GUSSMAN

BALDWIN No. 2

NE NW NW 30-9-20W  
Rooks County, Kansas

Comm: 12-11-51  
Comp: 12-21-51

Casing: 8-5/8" 176' w/125 sax  
5-1/2" 3883' w/100 sax

Formations	Depth
Clay, sand and shell	180
Shale, shell and sand	910
Shale, shell, sand, red bed	1595
Red bed and shale	1800
Anhydrite	1840
Shale and shells	1875
Broken lime and shale	2255
Broken lime	2290
Lime and shale	2590
Lime	2660
Lime and shale	3558
Lime	3774
Lime and Conglomerate	3830
Conglomerate and shale	3873
Arbuckle	3878

Geological Tops

Heebner Shale	3540
Toronto Lime	3563
Lansing-Kansas City	3579
Bese Kansas City	3798
Simpson Shale	3863
Arbuckle	3873

STATE OF KANSAS        )  
  ) SS:  
COUNTY OF SEDGWICK  )

L. C. Hay, of lawful age, deposes and states that the above formations and depths are correct as taken from the daily drilling log of the Baldwin No. 2 Well in the NE NW NW 30-9-20W, Rooks County, Kansas.

Subscribed and sworn to before me this 27th day of December, 1951.

*L. C. Hay*  
\_\_\_\_\_

*Nola Babb*  
\_\_\_\_\_  
Nola Babb  
Notary Public

My commission expires Nov. 3, 1952.

**PLUGGING**  
FILE SEC 30 T 9 R 20  
PAGE 147 LINE 25