


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Rooks County, Sec. 17 Twp. 9S Rge. 20 (E) (W)

NORTH



Locate well correctly on above Section Plat

Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines SE SW SE
Lease Owner Anderson Prichard Oil Corp.
Lease Name Box 112, Great Bend Pfannenstiel Well No. 1
Office Address Box 112, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 4-17 19.53
Application for plugging filed 4-17 19.53
Application for plugging approved 4-17 19.53
Plugging commenced 4-18 19.53
Plugging completed 4-18 19.53
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19.
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. Elden Petty
Producing formation Depth to top Bottom Total Depth of Well 3885 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	254'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Heavy Mud 3885 to 240'
Bottom Plug at 240' w/15 sax cement
Heavy mud to 40'
Top Plug at 40' w/10 sax cement
to surface

RECEIVED
STATE CORPORATION COMMISSION
APR 24 1953
CONSERVATION DIVISION
WICHITA, KANSAS

Plugging Contractor:
Transit Corporation
Oklahoma City, Oklahoma

(If additional description is necessary, use BACK of this sheet)


Correspondence regarding this well should be addressed to Anderson Prichard Oil Corporation
Address Box 112, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.
Gerald M. Dougherty (employee of owner) or (owner of interest) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Gerald M. Dougherty
P. O. Box 112, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 23 day of April, 1953



Thaddeus M. Hankins
Notary Public.

PLUGGING
FILE SEC 17 T 9 R 20 W
BOOK PAGE 94 LINE 28

TRANSIT CORPORATION

ANDERSON -PRICHARD - "PFANNENSTIEL #1"

SE/4,SW/4,SE/4 Sec.17-9-20W
Rooks Co.,Kansas

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>
Sand	0	40
Shale & Shells	40	254
Shale & Shells	254	515
Shale & Lime Shells	515	1000
Shale & Shells	1000	1240
Sand	1240	1485
Red Bed,Shale & Shells	1485	1740
Anhydrite	1740	1780
Shale & Shells	1780	1790
Shells,Shale & Red Bed	1790	2035
Shale & Shells	2035	2365
Lime & Shale	2365	2700
Lime	2700	2760
Sandy Shale & Shells	2760	2910
Lime & Shale Sandy	2910	3005
Shale & Shells	3005	3290
Lime & Shale	3290	3335
Lime & Shale	3335	3410
Lime	3410	3785
Shale & Lime	3785	3813
Shale & Cherty Lime	3813	3819
Lime & Chert	3819	3846
Cherty Lime	3846	3849
Cherty Lime & Shale	3849	3873
Total Depth		3885

COMMENCED: April 2, 1953

COMPLETED: April 18, 1953

Depth 254
8-5/8 CSA at 258'. Cemented with
200 sacks cement, 2 sks. chloride added.

I hereby certify the foregoing to be a true and accurate Driller's Log for the formations encountered in the above well.

TRANSIT CORPORATION

By: *C. W. Rodson*

Subscribed and sworn to before me this 22nd day of April, 1953.

My commission expires Feb. 14, 1957

Evelyn Culver
Evelyn Culver, Notary Public

PLUGGING

FILE SEC 17 T 9 R 204

BOOK PAGE 24 LINE 28

4/24/53