


15-163-19233-0000

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Rooks County. Sec. 17 Twp. 9S Rge. 20 (E) W (W)
Location as "NE/CNW/SW" or footage from lines SW SE NW
Lease Owner Anderson-Prichard Oil Corporation
Lease Name Pfannenstiel "A" Well No. 1
Office Address Liberty Bank Bldg. - Oklahoma City, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed April 10 19 59
Application for plugging filed April 10 19 59
Application for plugging approved April 10 19 59
Plugging commenced April 10 19 59
Plugging completed April 10 19 59
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well A. D. Fabricius - Hill City, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3858 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	197'	8 5/8"	197'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

From 3858' to 600' - heavy rotary mud
600' to 538' - plug, 1/2 sack hulls & 20 sacks cement
538' to 195' - heavy rotary mud
195' to 133' - plug, 1/2 sack hulls & 20 sacks cement
133' to 40' - heavy rotary mud
40' to 6' - plug, 1/2 sack hulls & 10 sacks cement
6' to 0 - cellar

RECEIVED
STAT. CORPORATION COMMISSION
APR 17 1959
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Peel Brothers, Inc.
Address P.O. Box 359 - Hoisington, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.
Peel Brothers, Inc. (employee of owner) or (~~owner~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. PEEL BROTHERS, INC.

(Signature) Jack Matlock
P.O. Box 359 - Hoisington, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 14th day of April 19 59

My commission expires April 27, 1960 Luth Brant Notary Public.

PLUGGING
FILE SEC. 17 T. 9 R. 20w
BOOK PAGE 31 LINE 28

15-163-19233-00-00

DRILLERS' LOG

Well Owner:	Anderson-Prichard Oil Corporation	SW SE NW
Farm Name:	Pfannenstiel "A" Well No. 1	Sec. 17-9S-20W
Commenced:	4/1/59	
Completed:	4/10/59	Rooks County, Kansas
Total Depth:	3858'	Elevation:
Casing:	8 5/8" @ 197' cemented	Production: Dry
Contractor:	Peel Brothers, Inc.	

Figures below indicate bottoms of formations:

Shale & sand	0 -	197
Shale		530
Shale & sand		1100
Sand		1250
Shale		1680
Shale & sand		1750
Red bed		1769
Anhydrite		1805
Shale		1965
Shale & red bed		2350
Shale & lime		2625
Lime		2960
Lime & shale		3590
Lime		3783
Lime & Cong.		3845
Lime		3858
Total Depth		3858

This is to certify that the above information is to the best of our knowledge, true and correct.


PEEL BROTHERS, INC.

BY *James M. Mattick*

SUBSCRIBED AND SWORN to before me this 14th day of April, 1959

My commission expires: April 27, 1960

Luick Brack
Notary Public



RECEIVED
STATE CORPORATION COMMISSION
APR 17 1959
CONSERVATION DIVISION
Wichita, Kansas
4/17/59

PLUGGING
FILE SEC. 17 T. 9 R. 20W
BOOK PAGE 31 LINE 28