

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Rooks County, Sec. 21 Twp 9 Rge 20 (E) (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines C-SE/4 SE/4 SE/4

Lease Owner Midstates Oil Corporation

Lease Name Florence Fesler Well No. 1

Office Address 518 National Bank of Tulsa Building - Tulsa, Okla.

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed March 22, 19 50

Application for plugging filed March 22, 19 50

Application for plugging approved March 22, 19 50

Plugging commenced March 22, 19 50

Plugging completed March 23, 19 50

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Petty

Producing formation None Depth to top Bottom Total Depth of Well 3915 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put In | Pulled Out |
|-----------|---------|------|----|--------|--------|------------|
| None | | | | 8-5/8" | 295' | None |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Well filled with heavy mud from bottom to 290' from surface, wood plug placed at this point and 15 sacks of cement mixed by Halliburton and pumped in through drill pipe. Casing then filled with mud to within 40 feet of surface, wood plug set at this point. 10 sacks of cement mixed by Halliburton and pumped in casing through drill pipe.

03-27-1950

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Midstates Oil Corporation
Address P.O. Box 151 - Hays, Kansas

STATE OF Kansas, COUNTY OF Rooks, ss.
J.O. Goes - Dist. Supt. (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well, as filed and that the same are true and correct. So help me God.

(Signature) J.O. Goes

P.O. Box 151 - Hays, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 25 day of March, 1950

My Commission Expires June 7, 1952

Dale M. Stagner Notary Public.

My commission expires

FILE SEC-21-1-9-1200
BOOK PAGE 144 LINE 39

15-163-04031-00-00

WELL LOG

Operator: Midstates Oil Corporation Farm Name: Florence Fesler No.1
 Location: SE SE SE Section 21-9S-20W Pool Name: Northampton
 County: Rooks State: Kansas
 Commencement Date: March 11, 1950 Completion Date: March 23, 1950
 Elevation: 2244' D. F. Status of Well: Dry Hole

FORMATION RECORD

| <u>From</u> | <u>To</u> | |
|-------------|-----------|------------------|
| 0 | 75 | |
| 75 | 295 | |
| 295 | 460 | Shale |
| 460 | 500 | Sand |
| 500 | 645 | Shale-Shells |
| 645 | 935 | Shale-Shells |
| 935 | 1070 | Sand-Shale stks. |
| 1070 | 1215 | Shale-Shells |
| 1215 | 1450 | Sand-Shale Stks. |
| 1450 | 1630 | Sand-Shale |
| 1630 | 1735 | Shale-Red Ved |
| 1735 | 1755 | Anhydrite |
| 1755 | 1765 | Anhydrite |
| 1765 | 1930 | Shale-Shells |
| 1930 | 2160 | Shale-Shells |
| 2160 | 2355 | Shale-Lime |
| 2355 | 2485 | Lime, Broken |
| 2485 | 2600 | Lime-Shale |
| 2600 | 2685 | Broken Lime |
| 2685 | 2800 | Lime-Shale |
| 2890 | 2980 | Lime-Shale |
| 2980 | 3055 | Lime-Shale |
| 3055 | 3140 | Lime-Shale |
| 3140 | 3220 | Lime- Shale |
| 3220 | 3340 | Lime-Shale |
| 3340 | 3430 | Lime-Shale |
| 3430 | 3470 | Lime-Shale |
| 3470 | 3530 | Lime-Shale |
| 3530 | 3580 | Lime |
| 3580 | 3620 | Lime |
| 3620 | 3660 | Lime |
| 3660 | 3720 | Lime |
| 3720 | 3780 | Lime |
| 3780 | 3815 | Lime |
| 3815 | 3845 | Lime-Shale |
| 3845 | 3915 | Lime |

CASING LEFT IN HOLE AFTER
COMPLETION OF THE WELL

Set 295' 8-5/8" OD Surface Casing.

STATE OF OKLAHOMA, COUNTY OF TULSA) ss.


The undersigned certifies that to the best of his knowledge and belief, the above facts are true and correct.

MIDSTATES OIL CORPORATION

By Geo. M. Vandavey
Vice President

Subscribed and sworn to before me this 17th day of April, 1950.

BRATCHER E. PARK, Notary Public
in and for Tulsa County, Okla.
My commission expires June 10, 1953



Bratcher E. Park
Notary Public

PLUGGING
FILE SEC 21-9-R20
39