

15-163-00691-00-00


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Rooks County. Sec. 24 Twp. 9S Rge. XX 20 (W)
Location as "NE/CNW/SW" or footage from lines C-NE-NW-NE
Lease Owner Sunray Oil Corporation
Lease Name Choquette Well No. 1
Office Address Box 195, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed March 14 19 54
Application for plugging filed March 16 19 54
Application for plugging approved March 17 19 54
Plugging commenced March 14 19 54
Plugging completed March 14 19 54
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation none Depth to top _____ Bottom _____ Total Depth of Well 3680 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Topeka		3107		8 5/8	210	none
Heebner		3313				
Toronto		3338				
Lsg-KC	water	3353	3572			
Conglomerate	water	3612				
Simpson Shale	water	3623				
Simpson Dolomite	water	3626				
Arbuckle	water	3664	3680			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mudded hole from 3680' to 210' and ran 20 sax cement. Mudded hole to 40' and ran 10 sax cement. Dry hole plugged and abandoned.

Well log attached.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Stickle Drilling Company
Address Tulsa, Oklahoma


STATE OF Kansas, COUNTY OF Barton
Robert K. Crouch (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Robert K. Crouch

Box 195, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 2nd day of April, 1954

My commission expires December 24, 1956



W. Stickle
Notary Public.

PLUGGING
FILE SEC 24 T 9 R 20
BOOK PAGE 20 LINE 14

FILED
04-03-1954
APR 3 1954
CONSERVATION DIVISION
Wichita, Kansas

15-163-00691-00-00

Sunray Oil Corporation
Tulsa, Oklahoma

Tulsa, Oklahoma
March 17, 1954

CONTRACTOR: Stickle Drilling Company
Drilling Commenced: March 2, 1954
Drilling Completed: March 14, 1954

Choquette #1 NE-NW-NE
Section 24-9S-20W, Rooks
County, Kansas.

DRILLERS LOG

Shale & Shells	0-700
Red Rock & Shale	700-950
Shale	950-1150
Shale & Shells	1150-1580
Anhydrite	1580-1625
Shale & Shells	1625-1790
Shale & Lime	1790-2265
Lime & Shale	2265-2365
Lime	2365-2430
Shale	2430-2480
Lime & Shale	2480-2618
Shale & Lime	2618-2810
Lime & Shale	2810-2975
Shale & Lime	2975-3106
Lime & Shale	3106-3209
Lime	3209-3572
Shale & Lime	3572-3603
Lime	3603-3616
Conglomerate - No formation shown -	3616-3680 TD

I, Frank E. Stickle hereby certify the above to be a true and complete Drillers Log of Sunray Oil Corporation's Choquette #1 NE-NW-NE-Section 24-9S-20W, Rooks County, Kansas.

Frank E. Stickle
Frank E. Stickle

Lillian T. Bonham
Notary Public

February 13, 1956

My Commission Expires

