

15-163-00879-00-00


WELL PLUGGING RECORD

STATE OF KANSAS STATE CORPORATION COMMISSION

Give All Information Completely Make Required Affidavit Mail or Deliver Report to: Conservation Division State Corporation Commission 800 Bittling Building Wichita, Kansas

Rooks County. Sec. 25 Twp. Rge. 20 XXXXXX (W)

Location as "NE/CNW&SW&" or footage from lines NW SE SW Lease Owner K & E-Oil Trading Assoc. Inc. Lease Name Steeples "A" Well No. #1 Office Address 1006 Central Bldg., Wichita, Kansas Character of Well (completed as Oil, Gas or Dry Hole) dry hole Date well completed Oct. 2, 1955 Application for plugging filed Oct. 2, 1955 Application for plugging approved Oct. 2, 1955 Plugging commenced Oct. 2, 1955 Plugging completed Oct. 2, 1955 Reason for abandonment of well or producing formation commercial quantities of oil not found



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19 Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty Producing formation Depth to top Bottom Total Depth of Well Feet Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Table with 7 columns: FORMATION, CONTENT, FROM, TO, SIZE, PUT IN, PULLED OUT. Row 1: 8 5/8, 202, none.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole to 190' set plug 1/2 sk of hulls mixed 15 sks cement. Filled hole to 40' set plug & 1/2 sk hulls made good solid bridge held wt. of kelly and swivel - mixed 10 sks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor K & E Drilling, Inc. Address 1006 Central Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss. Dale Silcott (employee of owner) or XXXXXX of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dale Silcott 1006 Central Bldg., Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 5th day of October, 1955 June 25, 1956



RECEIVED Notary Public STATE CORPORATION COMMISSION

OCT 6 - 1955 10-06-1955 CONSERVATION DIVISION Wichita, Kansas

PLUGGING FILE SEC 25 T 9 R 20 W BOOK PAGE 6 LINE 17

15-163-00879-00-00

K & E Drilling, Inc, - Oil Trading Associates, Inc.  
Steeple A - #1

NW SE SW Section 25-9S-20W  
Rooks County, Kansas

Comm: 9-20-55  
Comp: 10-2-55  
Total Depth: 3755'

Casing

Cement

8 5/8" Set @ 202'

140 sacks

FORMATION

DEPTH


Sand and Shale	0 - 180
Shale	180 - 790
Shale - shells	790 - 1155
Sand	1155 - 1360
Red bed	1360 - 1640
Anhydrite	1640 - 1680
Shale & shells	1680 - 1963
Shale lime	1963 - 2200
Lime & shale	2200 - 2395
Lime	2395 - 2620
Lime - shale	2620 - 2745
Lime	2745 - 2795
Lime & shale	2795 - 3320
Lime	3320 - 3350
Lime & shale	3350 - 3390
Lime	3390 - 3695
Lime shale	3695 - 3745
Lime Arbuckle	3745 - 3755

STATE OF KANSAS )  
                              ) SS  
SEDGWICK COUNTY )

I hereby certify that the above information is true and correct to the best of my knowledge.



Subscribed and sworn to before me this 5th day of October, 1955.

  
Notary Public

My commission expires: June 25, 1956

**PLUGGING**  
FILE SEC 25 T 9 R 20W  
BOOK PAGE 6 LINE 17

RECORDED  
STATE COMMISSION  
OCT 6 - 1955  
CONSERVATION DIVISION  
Wichita, Kan