

15-163-00915-00-00


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

ROOKS County. Sec. 25 Twp. 9S Rge. 20W (E) (W)

Location as "NE/CNW&SW&" or footage from lines NW SW SW  
Lease Owner K & E DRILLING, INC., ET AL  
Lease Name STEEPLES 'A-D' Well No. 1  
Office Address 719 Union Center, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) D & A  
Date well completed June 8th, 1959 19  
Application for plugging filed June 8th, 1959 19  
Application for plugging approved June 8th, 1959 19  
Plugging commenced June 8th, 1959 19  
Plugging completed June 8th, 1959 19  
Reason for abandonment of well or producing formation \_\_\_\_\_

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well \_\_\_\_\_  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3794 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	207'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled with heavy mud to 600' set plug  
with 20 sx cement thru drill pipe. Filled  
with heavy mud to 180' set plug with 15  
sx cement thru drill pipe. Filled with  
heavy mud to 40' set solid bridge with  
10 sx cement to base of cellar.  
Job Complete 6-8-59

RECEIVED  
STATE CORPORATION COMMISSION


JUN 11 1959  
06-11-1959  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor K & E DRILLING, INC.  
Address 719 Union Center, Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
Dale Silcott (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dale Silcott  
Dale Silcott, of K & E DRILLING, INC.  
719 Union Center, Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 10th day of June, 19 59  
My commission expires August 11h, 1962.  
Patricia M. Edwards, Notary Public.



PLUGGING  
FILE SEC 25 T 9 R 20W  
BOOK PAGE 44 LINE 31

15-163-00915-00-00

# DRILLER'S WELL LOG

OPERATOR: K & E DRILLING, INC.  
719 Union Center  
Wichita 2, Kansas

WELL NAME: #1 STEEPLES 'A-D'

LOCATION: NW SW SW  
Sec. 25-9S-20W  
Rooks County, Kansas

CONTRACTOR: K & E DRILLING, INC.  
719 UNION CENTER BLDG.  
WICHITA, KANSAS

COMMENCED: May 31st, 1959

CASING RECORD: 8-5/8" @ 207' (145 sx cmt)

COMPLETED: June 8th, 1959

ELEVATION: 2229' KB

ROTARY TOTAL DEPTH: 3497'

PRODUCTION: D & A

## FORMATION RECORD

Depths shown indicate bottom of formations encountered.

Cellar	8
Sand	60
Shale & Shells	207
Shale	675
Sand & Shale	1155
Sand	1390
Red Bed	1660
Anhydrite	1700
Shale & Shells	2360
Lime & Shale	2530
Lime & Shale	2835
Lime	2945
Lime & Shale	3220
Shale & Lime	3413
Lime	3690
Lime & Shale	3745
Conglomerate Shale	3758
Lime	3794
R.T.D.	3794

RECEIVED  
STATE CORPORATION COMMISSION

JUN 11 1959

CONSERVATION DIVISION  
Wichita, Kansas

### CERTIFICATION

State of KANSAS }  
County of SEDGWICK } ss:

I, Dale Silcott, of K&E DRILLING, INC., upon oath state that the above and foregoing is a true and correct copy of the Driller's Log of the above named well.

*Dale Silcott*  
Dale Silcott

Subscribed and sworn to before me this 10th day of June, 1959.

*Patricia M. Edwards*  
Patricia M. Edwards, Notary Public.

My Commission expires: August 11th, 1962.



PLUGGING		
FILE	SEC. 25 T9	R. 20W
BOOK	PAGE 44	LINE 31

