

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

15-163-20501-00-00

SEP 4 1973
09-04-73
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Moore of C & G Drilg. has this date requested permission to plug the following described well:

Mr. Moore guarantees payment of the plugging fee.

Operator's full Name: Thornton E. Anderson

Complete Address: 710 Union Nat'l Bldg., Wichita, Ks.

Lease Name: Husted Well No. 1

Location: NE NW SW Sec. 1 Twp. 10 Rge. (E)(W) 19

County: Rooks Total Depth 3305' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Moore was instructed to plug the well as follows:
Gum pits, circulate heavy mud, set cementing plug at 640' and displace
70 sk cmt thru drill pipe. Heavy mud to 240' set cementing plug and
displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing plug,
1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Leo F. Masser
Conservation Division Agent