



15-163-20313-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JUN 29 1970
CONSERVATION DIVISION
Wichita, Kansas
06-29-1970

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Mason of Dunne -Gardner has this

date requested permission to plug the following described well:

Mr. Mason guarantees payment of the plugging fee.

Operator's full Name: Thunderbird Drilling

Complete Address: Box 18412 Wichita

Lease Name: Collins Well No. 1

Location: NW NW NW Sec. 23 Twp. 10 Rge. (E)(W) 19

County: Rooks Total Depth 3733 Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Mason was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 660' and displace
70 sk cmt thru drill pipe. Heavy mud to 240' set cementing plug and
displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing
plug, 1/2 sk hulls and 10 sk cmt to base of cellar/

Very truly yours,

Leo J. Massey
Conservation Division Agent