



ROBERT B. DOCKING Governor  
 DALE E. SAFFELS Chairman  
 JULES V. DOTY Commissioner  
 JAMES O. GREENLEAF Commissioner  
 RAYMOND B. HARVEY Secretary  
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

212 N. Market

WICHITA, KANSAS 67202

RECEIVED  
STATE CORPORATION COMMISSION

APR 28 1969

CONSERVATION DIVISION  
Wichita, Kansas

04-28-1969

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. Lewis Brock  
 Administrator  
 500 Insurance Building  
 Wichita, Kansas 67202

15-163-20199-00-00

Dear Sir:

Mr. Kolhrus of Sage Drlg. has this

date requested permission to plug the following described well:

Mr. Kolhrus guarantees payment of the plugging fee.

Operator's full Name: Thunderbird Drilling, Inc.

Complete Address: 400 N. Woodlawn Wichita, Ks.

Lease Name: Winters Well No. 1

Location: NE NW NE Sec. 22 Twp. 10 Rge. 19W (E) (W)

County: Rooks Total Depth 3719' Oil Well

Gas Well  Input Well  SWD Well  D & A  Lost Hole

Mr. Kolhrus was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 600' and displace

70 sk cmt thru drill pipe. Heavy mud to 240' set cementing plug and

displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing

plug., 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Geo. J. Massey  
Conservation Division Agent