

State of Kansas



15-163-20018-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
APR 27 1967
04-27-1967
CONSERVATION DIVISION
WICHITA, KANSAS

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Crowe of Garvey Drlg. Inc. has this

date requested permission to plug the following described well:

Mr. Crowe guarantees payment of the plugging fee.

Operator's full Name: Petroleum Inc.

Complete Address: 300 West Douglas Wichita, Kansas

Lease Name: Steeples "D" Well No. 1

Location: SE NW SW Sec. 24 Twp. 10 Rge. 19 (E)(W) X

County Rooks Total Depth 3621 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Crowe was instructed to plug the well as follows:

Gun pits. circulate heavy md, set cementing plug at 540' and displace
20 sc cement thru drill pipe. Heavy mud to 210' set cementing plug and
displace 20 sc cement thru drill pipe. Heavy mud to 40' set cementing plug
1/2 sc hulls and 8 sc cement to base of cellar. Plug rat hole with 2 sc
cement.

Very truly yours,

Lew F. Massey
Conservation Division Agent