



JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

15-163-21241-00-00

VERBAL PERMIT FORM
(To be filed by Plugging Agent)

Dear Sir:

Mr. Rod Funk of Big Springs Dlg has this date requested permission to plug the following described well:

Operator's Full Name: Arrowhead Petroleum

Complete Address: P.O. Box 8287 Munger St. Wichita, Kans

Lease Name: Danuel Well No. # 3

Location: 25'N-25'E-C-SW-SW-SW Sec. 25 Twp. 10 Rge. 19 (E) (W)

County: Rooks Total Depth: 3530 FT

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Funk was instructed to plug the well as follows:

- 8 7/8" 209 FT SR ccc w/ 145 ST SW Set.
- Order 110 ST 50/50 Pozimix 6% Gel. + 8 7/8" Plug.
- Spot with Drill Stem - with Heavy Mud Between all Plug.
- 1ST Plug @ 720 w/ 65 ST end.
- 2ND Plug @ 240 w/ 30 ST end.
- 3RD Plug - solid Bridge - Plug @ 40 FT to 0 w/ 10 ST end.
- 5TH In Cat Hole.

Very truly yours, (By Sign End)

Marion Schmidt
Conservation Division Agent

RECEIVED
STATE CORPORATION COMMISSION
APR 13 1981
04-13-1981
CONSERVATION DIVISION
Wichita, Kansas