



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
245 North Water
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

SEP 25 1978
09-25-1978
CONSERVATION DIVISION
Wichita, Kansas

15-163-20838-00-00

J. Lewis Brock
Administrator
245 North Water
Wichita, Kansas 67202

Dear Sir:

Mr. Ragsdal of Big Springs Drlg. has this date requested permission to plug the following described well:

Mr. Ragsdal guarantees payment of the plugging fee.

Operator's full Name: Arrowhead Petroleum, Inc.

Complete Address: Box 8287, Munjor Station, Wichita, Ks.

Lease Name: Steeples Well No. 1

Location: SE SW NW Sec. 25 Twp. 10 Rge. (E)(W) 19

County: Rooks Total Depth 3530' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Ragsdal was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set 70 sk cmt plug at 600' thru drill

pipe. Heavy mud to 215' set 20 sk cmt plug thru drill pipe. Heavy

mud to 40' set solid bridge & 10 sk cmt plug to base of cellar.

Very truly yours,

Lee M. ...
Conservation Division Agent