



ROBERT B. DOCKING Governor
 WILLIAM L. MITCHELL Chairman
 JAMES O. GREENLEAF Commissioner
 DALE E. SAFFELS Commissioner
 RAYMOND B. HARVEY Secretary
 E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

15-163-20090-00-00

RECEIVED
 STATE CORPORATION COMMISSION
 JAN 24 1968
 CONSERVATION DIVISION
 Wichita, Kansas

01-24-1968

J. P. Roberts
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Flake of Woodman- Iannitti Drlg. has this
 date requested permission to plug the following described well:

Mr. Flake guarantees payment of the plugging fee.

Operator's full Name: W. F. Newton

Complete Address: P. O. Box 250 Conroe, Texas

Lease Name: Steeple Well No. 1

Location: C E/2 W/2 NW Sec. 25 Twp. 10 Rge. 19 (E)(W) W

County: Rooks Total Depth 3256 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Flake was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 800' and displace

70 sc cement thru drill pipe. Heavy mud to 210' set cementing plug and

displace 20 sc cement thru drill pipe. Heavy mud to 40' set cementing

plug, 1/2 sc hulls and 10 sc cementto base of cellar. Plug rat hole with

2 sc cement.

Very truly yours,

Law A. Massey
 Conservation Division Agent