



15-065-20515
Conservation-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

JAN 3 1972

CONSERVATION DIVISION
Wichita, Kansas

1-3-72

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Jim Lahar of B & B Drilling, Incorporated has this date requested permission to plug the following described well:

Mr. Lahar guarantees payment of the plugging fee.

Operator's full Name: Kedco Corp, National Oil Co., & B & B Drlg., Inc.,

Complete Address: 816 Union Center Building, Wichita, Kansas.

Lease Name: Teall Well No. 1

Location: SE-SW-NE Sec. 8 Twp. 9 Rge. (E)(W) 21

County: Graham Total Depth 3865' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Lahar was instructed to plug the well as follows:

204'--8 5/8" Surface casing, cement circulated with-??

Top of Dakota section @ 725'.

Circulate hole with heavy mud. Pull DP to 950' and displace 110 Cu. Ft. cement thru DP. Pull DP to 215' and displace 30 Cu. Ft. cement thru DP, Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

Conservation Division Agent