



15-065-20289-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
DEC 11 1969
CONSERVATION DIVISION
Wichita, Kansas
12-11-69

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Vic Gustus of Leben Drilling, Incorporated has this date requested permission to plug the following described well:

Mr. Gustus guarantees payment of the plugging fee.

Operator's full Name: Tilco, et al,

Complete Address: 200 Sutton Place, Wichita, Kansas.

Lease Name: McClellan Well No. 1

Location: NW-SW-NE Sec. 28 Twp. 9 Rge. (E)(W) 21

County: Graham Total Depth 3940' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Gustus was instructed to plug the well as follows:

209'-8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 750'.

Circulate hole with heavy mud. Pull DP to 975' and displace 100 Sx.
cement thru DP. Pull DP to 215' and displace 25 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

Conservation Division Agent