

State of Kansas



15-065-01141-00-00

FORM - CP-2
Rev. 9-8-64

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL Chairman
ALVIN P. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
DEC 15 1964
12-15-64
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Adminstrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Darrell Kelso of Knight Casing Pulling Co. has this

date requested permission to plug the following described well:
Morgenstern & Specter

Mr. Kelso guarantees payment of the plugging fee.

Operator's full Name: Morgenstern & Specter, Incorporated.

Complete Address: Box #661, Russell, Kansas.

Lease Name: C. Smith Well No. A-1

Location: CSW-SW-SE Sec. 31 Twp. 9 Rgs. (E) (W) 21

County Graham Total Depth 3885 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Kelso was instructed to plug the well as follows:

211'--8 5/8" Surface pipe, cement circulated.
3881'--5 1/2" Production casing cemented with 100 Sx.
Well squeezed in Dakota Sands.

Sand well back to 3870' and set 5 Sx. cement with dump bailer.

Find Fluid level , fill hole with heavy mud to 600' π , set

rock bridge and fill to bottom of cellar with Redi*Mix.

Very truly yours,

W. L. Nichols
Conservation Division Agent