

State of Kansas



15-065-20083-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Jim Lahar of B & B Drlg. Co. Inc., has this
date requested permission to plug the following described well:

Mr. Lahar guarantees payment of the plugging fee.

Operator's full Name: Allison & Black,

Complete Address: 1415 Wichita Plaza, Wichita, Kansas.

Lease Name: Lambert Well No. 2

Location: 50' East of SE-NW-SW Sec. 36 Twp. 9 Rge. (E)(W) 21

County Graham Total Depth 3895' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Lahar was instructed to plug the well as follows:

219'--8 5/8" Surface pipe, cement circulated with 160 Sx.
Dakota section from 990' to 1160'.

Circulate hole with heavy mud. Pull DP to 1180' and displace 160 Sx.
cement thru DP. Pull DP to 240' and displace 20 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

RECEIVED
STATE CORPORATION COMMISSION
Very truly yours,

SEP 15 1967

9-15-67

CONSERVATION DIVISION
Wichita, Kansas

R. L. Nichols
Conservation Division Agent