

KANSAS

*AL*  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

15-179-20316-00-00

RECEIVED  
STATE CORPORATION COMMISSION

JUL 3 1972

CONSERVATION DIVISION  
Wichita, Kansas

7-3-72

Operator's Full Name Okmar Oil Company,

Complete Address 1130 Vickers KSB&T Building, Wichita, Kansas.

Lease Name Geerdes <sup>KCC</sup> A <sub>cap</sub> Well No. 4-1

Location CNW-SE Sec. 30 Twp. 8 Rge. (E) (W) 29

County Sheridan Total Depth 2548'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated       

Plugging Contractor Sage Drilling Company, Incorporated,

Address 500 Bitting Bldg., Wichita, Kansas License No.       

Operation Completed: Hour 11:00 PM Day 30 Month 6 Year 1972

The above well was plugged as follows:

263'--8 5/8" Surface casing, cement circulated with 225 Sx.  
Top of Dakota section @ 1300'.

Circulated hole with heavy mud. Pulled DP to 1525' and displaced 110 Cu. Ft. cement  
thru DP from 1525' to 1200'. Pulled DP to 275' and displaced 30 Cu. Ft. cement thru  
DP from 275' to 200'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.  
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *A. L. Nichols*  
Well Plugging Supervisor

INVOICED  
DATE 7-5-72  
INV. NO. 5973-42