

KANSAS

Form CP-3  
Rev. 6-26-62

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

**RECEIVED**  
STATE CORPORATION COMMISSION

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

4/19/67

APR 19 1967

CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name John O. Farmer, Incorporated.

Complete Address: 370 West Wichita Ave., Russell, Kansas.

Lease Name Mosier Well No. B-2

Location SE-NE-SE Sec. 36 Twp. 8 Rge. (E) (W) 29

County Sheridan Total Depth 4130

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: Above

Address:      License No.     

Operation Completed: Hour 8:30AM Day 18 Month 4 Year 1967

The Above well was plugged as follows:

212'--8 5/8" Surface pipe, cement circulated with 130 Sx.

Circulated hole with heavy mud, set plug @ 600' and displaced 20 Sx.

cement thru DP. Heavy mud to 210', set plug with 1/4 sack hulls and dis-

placed 20 Sx. cement thru DP. Heavy mud to 40', set plug with 1/2 sack

hulls and 10 Sx. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

**INVOICED**

DATE 4-19-67

INV. NO. 5077-W

Signed: A. L. Nichol  
Well Plugging Supervisor