

KANSAS

Form CP-3  
Rev. 6-4-68

15-179-20381-00-00

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 6 - 1974  
CONSERVATION DIVISION  
Wichita, Kansas

5/6/74

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name John O. Farmer, Incorporated,  
Complete Address Box #352, Russell, Kansas.  
Lease Name Mosier Well No. C-1  
Location NW-SW-NW Sec. 36 Twp. 8 Rge. (E) (W) 29  
County Sheridan Total Depth 4160'  
Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X  
Other well as hereafter indicated       
Plugging Contractor Above  
Address      License No.       
Operation Completed: Hour 12:30 PM Day 3 Month 5 Year 1974

The above well was plugged as follows:

255'--8 5/8" Surface casing, cement circulated with 170 Sx.  
Top of Dakota section @ 1275'.

Circulated hole with heavy mud. Pulled DP to 1500' and displaced 110 Cu. Ft. cement  
thru DP from 1500' to 1175'. Pulled DP to 275' and displaced 30 Cu. Ft. cement thru  
DP from 275' to 200'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.  
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: H. L. Nichols  
Well Plugging Supervisor

INVOICED

DATE 5/8/74  
INV. NO. 9062-W