

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

15-179-20033-00-00

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 14 1967  
08-14-1967  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Leo J. Dreiling Oil Company,

Complete Address: Victoria, Kansas.

Lease Name Feldt Well No. 1

Location NE-SW Sec. 1 Twp. 8 Rge. (E) (W) 30

County Sheridan Total Depth 4275

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: L. J. Dreiling & Sons, Incorporated,

Address: Victoria, Kansas. License No. \_\_\_\_\_

Operation Completed: Hour 3:30PM Day 8 Month 8 Year 1967

The Above well was plugged as follows:

325'--8 5/8" Surface pipe, cement circulated with 175 Sx.  
Dakota section from 1800' to 1990'.

Circulated hole with heavy mud, pulled DP to 2010' and displaced 100 Sx.  
cement thru DP. Pulled DP to 330' and displaced 20 Sx. cement thru DP.  
pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom  
of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: M. L. Nichols  
Well Plugging Supervisor

INVOICED

DATE 8/14/67

INV. NO. 6133-W