

KANSAS

ll
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
AUG 5 1970
CONSERVATION DIVISION
Wichita, Kansas

5-179-20260-00-00

Operator's Full Name Shields Oil Producers, Incorporated, 08-05-1970

Complete Address Shields Building, Russell, Kansas.

Lease Name Kennedy Well No. A-1

Location SE-SE-NW Sec. 4 Twp. 8 Rge. (E) (W)30

County Sheridan Total Depth 4310'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Shields Drilling Company, Incorporated,

Address Shields Building, Russell, Kansas. License No.

Operation Completed: Hour 11:00 AM Day 31 Month 7 Year 1970

The above well was plugged as follows:

322'--8 5/8" Surface casing, cement circulated with 170 Sx.
Top of Dakota section @ 1525'.

Circulated hole with heavy mud. Pulled DP to 1750' and displaced 100 Sx. cement thru
DP from 1750' to 1425'. Pulled DP to 340' and displaced 20 Sx. cement thru DP from
340' to 280'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. L. Nichols
Well Plugging Supervisor

DATE 8/6/70
INV. NO. 2336-W