

KANSAS

Y
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
SEP 15 1970
CONSERVATION DIVISION
Wichita, Kansas
09-15-1970

15-179-20265-00-00

Operator's Full Name Shields Oil Producers, Incorporated,

Complete Address Shields Building, Russell, Kansas.

Lease Name Ibson Well No. 1

Location NE-NE-NW Sec. 14 Twp. 8 Rge. (E) (W) 30

County Sheridan Total Depth 4298'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Shields Drilling Company, Incorporated,

Address Shields Building, Russell, Kansas. License No.

Operation Completed: Hour 12:15 AM Day 11 Month 9 Year 1970

The above well was plugged as follows:

290'--8 5/8" Surface casing, cement circulated with 170 Sx.
Top of Dakota section @ 1450'.

Circulated hole with heavy mud. Pulled DP to 1675' and displaced 100 Sx. cement thru
DP from 1675' to 1350'. Pulled DP to 325' and displaced 25 Sx. cement thru DP from
325' to 250'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *M. L. Daniels*
Well Plugging Supervisor

INVOICED

DATE 9-15-70

INV. NO. 2540-W