

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

JUN 28 1972  
06-28-1972  
CONSERVATION DIVISION  
Wichita, Kansas

15-179-20315-00-00

Operator's Full Name Okmar Oil Company,

Complete Address 1130 Vickers KSB&T Building, Wichita, Kansas.

Lease Name Howard Well No. 1

Location SE-SE-NE Sec. 26 Twp. 8 Rge. (E) (W)30

County Sheridan Total Depth 4205'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Sage Drilling Company, Incorporated,

Address 500 Bitting Bldg., Wichita, Kansas. License No. \_\_\_\_\_

Operation Completed: Hour 11:30 AM Day 26 Month 6 Year 1972

The above well was plugged as follows:

266'--8 5/8" Surface casing, cement circulated with 225 Sx.  
Top of Dakota section @ 1350'.

Circulated hole with heavy mud. Pulled DP to 1575' and displaced 110 Cu. Ft. cement  
thru DP from 1575' to 1250'. Pulled DP to 280' and displaced 30 Cu. Ft. cement thru  
DP from 280' to 205'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.  
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: R. L. Nichols  
Well Plugging Supervisor

INVOICED  
DATE 6/29/72  
INV. NO. 5956-W