

KANSAS

*Al*

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 11 1969  
CONSERVATION DIVISION  
Wichita, Kansas  
03-11-1969

15-179-20185-00-00

Operator's Full Name Kaiser-Francis,

Complete Address: 909 Palace Building, Walsat, Oklahoma.

Lease Name Struckhoff Well No. 1

Location NE-NE-NE Sec. 29 Twp. 8 Rge. (E) (W) 30

County Sheridan Total Depth 4305'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: L. J. Dreiling & Sons, Incorporated,

Address: R. R. #2, Victoria, Kansas. License No.     

Operation Completed: Hour 2:30 PM Day 10 Month 3 Year 1969

The Above well was plugged as follows:

351'--8 5/8" Surface casing, cement circulated with 225 Sx.  
Top of Dakota section @ 1450'.

Circulated hole with heavy mud. Pulled DP to 1675' and displaced 100 Sx. cement thru  
DP from 1675' to 1350'. Pulled DP to 365' and displaced 20 Sx. cement thru DP from  
365' to 305'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to  
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *H. S. Nichols*  
Well Plugging Supervisor

INVOICED

DATE 3/11/69  
INV. NO. 9444-11