

KANSAS

Handwritten mark

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
SEP 20 1968
CONSERVATION DIVISION
Wichita, Kansas
09-20-1968

15-179-20132-00-00

Operator's Full Name Rains & Williamson Oil Company, Incorporated,

Complete Address: 1425 Wichita Plaza Building, Wichita, Kansas.

Lease Name McCormick Well No. 1

Location CSW-NW Sec. 35 Twp. 8 Rge. (E) (W) 30

County Sheridan Total Depth 4250'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Above

Address: License No.

Operation Completed: Hour 6:00AM Day 18 Month 9 Year 1968

The Above well was plugged as follows:

278'--8 5/8" Surface casing, cement circulated with 175 Sx.
Top of Dakota section @ 1425'.

Circulated hole with heavy mud. Pulled DP to 1650' and displaced 100 Sx. cement thru
DP from 1650' to 1325'. Pulled DP to 305' and displaced 20 Sx. cement thru DP from
305' to 245'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. D. Dichel
Well Plugging Supervisor

INVOICED
DATE 9/20/68
INV. NO. 8490-41