

KANSAS

Form CP-3
Rev. 6-4-68

14

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
FEB 19 1970
CONSERVATION DIVISION
Wichita, Kansas
02-19-1970

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-193-20013-00-00

Operator's Full Name Murfin Drilling Company,

Complete Address 617 Union Center Building, Wichita, Kansas.

Lease Name Christenson ^{KCC}
~~Christensen~~ ^{ZAP} Well No. 1

Location NE-NE-NE Sec. 34 Twp. 8 Rge. (E) (W) 31

County Thomas Total Depth 4645'

Abandoned Oil Well x Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Knight Casing Pulling Company, Incorporated,

Address Box #105, Chase, Kansas, License No. 624

Operation Completed: Hour 12:00 M Day 17 Month 2 Year 1970

The above well was plugged as follows:

250'--8 5/8" Surface casing, cement circulated with 275 Sx.
4613'--5 1/2" Production casing cemented on bottom with 150 Sx. Well plugged back to
4050'. Top perforations @4020'.

Sanded well back to 4000' and set 5 Sx. cement with dump bailer. Pulled 5 1/2" casing
and squeezed well initially with 5 sacks hulls and 3 sacks gel and followed with 100
Sx. cement from 1725' to 1400' then 28 sacks gel from 1400' to 280' and followed with
25 Sx. cement from 280' to 200' then 4 sacks gel from 200' to 40' and finally 10 Sx.
cement from 40' to bottom of cellar. Maximum pump-in pressure--300#. Final shut-in
pressure 100#. Recovered 1378' 5 1/2" casing. (Mudding and cementing by Halliburton.

I hereby certify that the above well was plugged as herein stated.

Signed: *W. L. Nichols*
Well Plugging Supervisor

INVOICED

DATE 2/19/70
INV. NO. 1452-u