

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

OCT 21 1969

CONSERVATION DIVISION
Wichita, Kansas

10-21-1969

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-193-20025-00-00

Operator's Full Name Murfin Drilling Company,

Complete Address 617 Union Center Building, Wichita, Kansas.

Lease Name Christensen Well No. 2

Location CSW-NE Sec. 34 Twp. 8 Rge. (E) (W) 31

County Thomas Total Depth 4300'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Above

Address License No.

Operation Completed: Hour 3:00 PM Day 14 Month 10 Year 1969

The above well was plugged as follows:

270'--8 5/8" Surface casing, cement circulated with 250 Sx.
Top of Dakota section @ 1400'.

Circulated hole with heavy mud. Pulled DP to 1625' and displaced 100 Sx. cement thru
DP from 1625' to 1300'. Pulled DP to 275' and displaced 20 Sx. cement thru DP from
275' to 215'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: N. L. Dickels
Well Plugging Supervisor

DATE 10/21/69
INV. NO. 695-4