

KANSAS

dl
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAR 23 1970
CONSERVATION DIVISION
Wichita, Kansas

3-23-70

J. Lewis Brock,
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-193-20028-0000

Operator's Full Name Donald C. Slawson,

Complete Address 408 One-Twenty Building, Wichita, Kansas,

Lease Name Ryan Well No. E-1

Location 145' So. of CNE-SW Sec. 27 Twp. 8 Rge. (E) (W) 32

County Thomas Total Depth 4690'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Slawson Drilling Company, Incorporated,

Address 408 One-Twenty Building, Wichita, License No. _____

Operation Completed: Hour 2:45 PM Day 19 Month 3 Year 1970

The above well was plugged as follows:

452'--8 5/8" Surface casing, cement circulated with 300 Sx.
Top of Dakota Section @ 1625'

Circulated hole with heavy mud. Pulled DP to 1850' and displaced 100 Sx. cement
thru DP from 1850' to 1525'. Pulled DP to 465' and displaced 25 Sx. cement thru DP
from 465' to 390'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement
to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *M. L. Nichols*
Well Plugging Supervisor

INVOICED

DATE 3/23/70
INV. NO. 1627-41