

KANSAS

Form CP-3  
Rev. 6-26-62

*R*

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

15-193-20004-00-00

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 15 1968  
CONSERVATION DIVISION  
Wichita, Kansas

7-15-68

Operator's Full Name Donald C. Slawson,

Complete Address: 408 One-Twenty Building, Wichita, Kansas.

Lease Name Younger Well No. A-1

Location CSW-NW Sec. 7 Twp. 8 Rge. (E) (W) 35

County Thomas Total Depth 3250

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Slawson Drilling Company, Incorporated,

Address: 408 One-Twenty Building, Wichita, Kans. License No. \_\_\_\_\_

Operation Completed: Hour 10:15AM Day 12 Month 7 Year 1968

The Above well was plugged as follows:

249'--8 5/8" Surface pipe, cement circulated with 190 Sx.  
Top of Dakota section @ 1630.

Circulated-hole-with-heavy mud. Pulled DP from bottom to 1860' and displaced 100 Sx.  
cement thru DP. from 1860' to 1540'. Pulled DP to 275' and displaced 20 Sx. cement  
thru DP from 275' to 215'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx.  
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *M. L. Nichols*  
Well Plugging Supervisor

DATE 7-15-68

INV. NO. 8122-w